



ENVIRONMENTAL HEALTH

GUADALUPE COUNTY

310 IH 10 W

Seguin, Texas 78155

Office: (830) 303-8858

eh-permits@co.guadalupe.tx.us

OSSF INSPECTION SCHEDULE

AEROBIC / ADVANCED SYSTEM

Installer II must be present at time of inspections and present copy of current license to inspector.

OPERATIONAL INSPECTION

- Tank set, full of water, and T's are installed as per design (uncovered)
- Disposal system and/or sprinklers are installed as per design (uncovered)
- Maintenance tag and chlorine treatment must be present
- Conduit openings into panel caulked
- Operational test will be conducted to complete the operational inspection

FINAL INSPECTION

- System must be covered with topsoil and seasonal grasses must be seeded over the disposal area in order to minimize run-off and erosion
- Risers installed *(if required)*

CONVENTIONAL SYSTEM

Installer I or II must be present at time of inspections and present copy of current license to inspector.

1ST INSPECTION

- Pipe from the structure to tank must be installed with a 2way cleanout and meet proper slope
- Tank set, full of water, and T's are installed as per design (uncovered)
- Disposal area must comply with the excavation requirements of TCEQ Chapter 285

2ND INSPECTION

- Disposal system is installed, level, and with geotextile *(if required)* as per design (uncovered)

FINAL INSPECTION

- System must be covered with topsoil and seasonal grasses must be seeded over the disposal area in order to minimize run-off and erosion
- Risers, berms and/or diversion ditches are installed *(if required)*

ALTERATIONS

INSPECTION

- Any portion of the septic being altered or repaired as per design (uncovered)

Request an OSSF inspection at least 24 hours before the requested time
Cancel an OSSF inspection at least 1 hour before the scheduled time
Submit a revision to the septic inspector at least 24 hours before the scheduled time