

# ENVIRONMENTAL HEALTH

**GUADALUPE COUNTY** 

310 IH 10 West Seguin, Texas 78155 Office: (830) 303-8858 <u>eh-permits@co.guadalupe.tx.us</u>

#### **OSSF INSPECTION SCHEDULE**

#### **AEROBIC / ADVANCED SYSTEM**

### Installer II must be present at the time of inspection(s) and present a copy of current license to the inspector.

OPERATIONAL INSPECTION

- Pipe from the structure to tank must be installed with a 2-way cleanout and meet minimum slope (1/8" per 1')
- Tank is set, full of water, and T's are installed as per design (uncovered)
- Disposal system and/or sprinklers are installed as per design (uncovered)
- Maintenance tag and chlorine treatment must be present

- Conduit openings into panel are caulked
- Conduct an operational test to complete the operational inspection

#### FINAL INSPECTION

- System must be covered with topsoil and seasonal grasses must be seeded over the disposal area in order to minimize run-off and erosion
- Risers installed (if required)

#### **CONVENTIONAL SYSTEM**

## Installer I or II must be present at the time of inspection(s) and present a copy of current license to the inspector.

1<sup>ST</sup> INSPECTION

- Pipe from the structure to tank must be installed with a 2-way cleanout and meet minimum slope (1/8" per 1')
- Tank is set, full of water, and T's are installed as per design (uncovered)
- Disposal area must comply with the excavation requirements of 30 TAC Chapter 285

2<sup>ND</sup> INSPECTION

- Disposal system is installed, level, and with geotextile (*if required*) as per design (uncovered) FINAL INSPECTION
  - System must be covered with topsoil and seasonal grasses must be seeded over the disposal area in order to minimize run-off and erosion
  - Risers, berms and/or diversion ditches are installed (if required)

.....

#### ALTERATIONS

INSPECTION

• Any portion of the septic being altered or repaired as per design (uncovered)

Request an OSSF inspection at least 24 hours before the requested time

### Cancel an OSSF inspection at least 1 hour before the scheduled time